

# FRANKLIN COUNTY

REPLY TO:  
BOARD OF COUNTY COMMISSIONERS  
33 MARKET STREET, SUITE 203  
APALACHICOLA, FL 32320  
(850) 653-8861, EXT. 100



ORIGINATING DEPARTMENT:  
FRANKLIN COUNTY ADMINISTRATION  
248 HIGHWAY 98  
EASTPOINT, FL 32328  
(850) 653-9783

## ADDENDUM #01: QUESTIONS AND ANSWERS DUNE CONSTRUCTION AND VEGETATION PROJECTS

**BID/RFP/RFQ NAME:** Dune Construction and Vegetation Projects

**DATE OF ADDENDUM:** October 3, 2025

**TO:** Interested Respondents

**CONTACT:** Erin Griffith, Fiscal Manager, [erin@franklincountyflorida.com](mailto:erin@franklincountyflorida.com), 850-653-5143

**RESPONSE DUE DATE:** Tuesday, November 4, 2025, 4:00 P.M. Eastern

**Question #01:** What is the final payment after the 180-day vegetation warranty period?

**Answer:** Payment procedures will follow Article 6 of the Agreement (Section 00520) in the bid advertisement.

**Question #02:** Can seeds come from outside of the panhandle?

**Answer:** Technical Specification 12.0 listed in the Construction Plans discusses source of the plant material.

**Statement 1:** Amend Technical Specification 9.0 (Surveys) with the following in order to improve volume placement calculations:

“At Carrabelle Beach Park, pre- and post-construction dune surveys shall be collected at construction baseline stations 0+00, 1+00, 2+00, 3+00, 3+30, 3+80, 4+00, 5+00, 6+00, 6+59, 7+00, 7+50, and 8+00 at a minimum. At Lighthouse Park, pre- and post-construction dune surveys shall be collected at construction baseline stations 0+00, 1+00, 2+00, 3+00, 4+00, and 4+50 at a minimum.”

**Statement 2:** Replace Technical Specification 10.0 (Sand Specifications) paragraph (A) with the following:

“All dune sand shall be obtained from a source landward of the coastal construction control line and be consistent the criteria specified in Rule 62B-33.005(7), Florida Administrative Code, and shall consist of sand which is similar to that already on the site in both grain size and coloration. This fill material shall be free of construction debris, rocks, or other foreign matter. The fill material may not contain more than 5% silt (percent

passing the #230 sieve) and no more than 5% shell content (percent retained on the #4 sieve).”